
Current status of Nuclear Data Production System at RAON

함철민, 추경호, 이상진, 편성재, 이광복, C. Ackers,
김미정, 김재천, 곽민식, 곽동현, 김동건, 신태수


Experimental system team
Institute of Rare Isotope Science (IRIS)





필요성


- ❖ 수십 MeV 에너지 영역의 중성자 유도 단면적 핵 데이터는 불충분하며 불확도가 큼.
- ❖ 물성변화시험, 국방, 비파괴검사, 반도체 검사 등 다양한 분야에서 고속 중성자 관련 핵 데이터에 대한 수요가 증가하고 있음.
- ❖ 가속기 구동 시스템(ADS), 방사성 폐기물 처리, 의료/산업 동위원소 생산 등 다양한 응용 분야에서 정밀한 핵 데이터 확보가 요구됨.



NDPS

SCL3-NDPS beamline

NDPS
Nuclear Data Production System



중성자 측정실 ToF room





표적실 Target room




빔수송실2 Beam transport room2





❖ Specification of NDPS


Beam ion	Proton, deuteron
Maximum Beam energy	49 MeV/u for deuteron 83 MeV/u for proton
Maximum Beam current	~10 μA
Target	C for white neutron Li for monoenergetic neutron
Bunch length	~ 1 nsec
Repetition rate	1 – 200 kHz
Flight length	5 – 40 m
Neutron flux	~ $10^8 \text{ cm}^{-2} \text{ sec}^{-1}$ at 5 m





n


Magnet



3D modeling



Dipole magnet



Quadrupole magnet



Steering magnet

Specification

1. Dipole magnet (1 ea)

Pole gap	80 mm
Maximum field	1.2 T
Effective length	570 mm
Power	17.6 kW

2. Quadrupole magnet (4 ea)

Aperture	70 mm
Max. gradient field	10 T/mm
Effective length	300 mm
Power	0.6 kW

3. Steering magnet (2 ea)


Pole gap	80 mm
Max. field integral	2.518 T mm
Power	22 W

Dipole magnet

Quadrupole magnet


steering magnet


Power supply



PS room

OPI program for the remote control







white neutrons

Carbon target


49 MeV/u deuteron





3D modeling



Inside of the chamber



Checking alignment




Neutron intensity at the end of the collimator
 $\approx 10^8$ neutrons/cm²/sec for 10 pμA




white neutrons




Carbon target




49 MeV/u deuteron



Remote control system for C target



Remote control system for C target








Target storage

C target chamber




← Monoenergetic neutrons

Lithium target





Neutron intensity at the end of the collimator
 $\approx 10^5 \text{ neutrons/cm}^2/\text{sec}$ for $10 \mu\text{A}$

Proton Beam Dump




3D Drawing




Target room

Radiation analysis




Design and photo of lead shield structure




J. C. Kim (IBS)






Neutron Collimator



Neutron distribution simulated by using MCNPX





E. Lee et al. NIMA 902 (2018) 138






n

Detector



Detectors in ToF room


Monitoring detectors
(PPAC, GEM or Micromegas)



Fission exp. chamber

ToF room

DAQ system




ToF room


2" EJ-301 liquid scintillator




PPAC (Parallel Plate Avalanche Counter)




From D. Moon (SKKU)




Neutron Beam Dump




Dose calculation with the concrete thickness change



Dose calculation with the different hole radius




MCNP simulation with the different beam dump structure






* Scattered neutrons: case 1 < case 2

- ❖ Concrete thickness = 330 cm
 - Beam dump = 200 cm
 - Wall thickness behind the dump 130 cm
- ❖ Hole radius = 30 cm
- ❖ Dump structure → case 1







Beam diagnostics



Control system

- ❖ Remote control system
for target, diagnostics, vacuum, and magnet control
- ❖ Programmable Logic Controllers (PLC) and
Experimental Physics and Industrial Control System (EPICS) based
- ❖ Developments of the system was completed in 2022.



Installation of gas storage

Outside of the building
2021.11

Plumbing of gas pipes for the detectors



ToF room
2022.01

installation of cable tray




Target Room
2022.02

Cabling for magnet power supply

ToF Room
2022.02


Plumbing of cooling water pipes




Target room

2022.03

Leak test



Plumbing of pneumatic pipes



solenoid valves

Target room
2022.07

- ❖ Main devices of NDPS were assembled and installed at the end of December 2021.
- ❖ Main devices of SCL3-NDPS beam line were assembled and installed at the end of December 2022.
- ❖ Remote control system for C target and target storage box was installed at the end of December of 2022.
- ❖ Development for control system were completed at the end of December of 2022.
- ❖ **Integral test and preparation of beam commissioning will be performed in 2023/2024.**
- ❖ **Beam commissioning is planned with proton beam or Ion beam(^{16}O and ^{40}Ar) in 2024.**
- ❖ **The beam will be provided to users starting from 2024.**


Collaborators



Korea Atomic Energy
Research Institute



SUNG KYUN KWAN UNIVERSITY



Collaboration are always welcome!!



Thank you !

