

20MeV/100MeV Proton Beam Lines of PEFP User Facility

Y. S. Cho, B. C. Chung, K. Y. Kim, K. R. Kim, Y. H. Kim, H. J. Kwon, J. H. Jang, and B. H. Choi
Proton Engineering Frontier Project, Korea Atomic Energy Research Institute, Daejeon, 305-353, Korea
choys@kaeri.re.kr

1. Introduction

The main concept of the PEFP proton beam facility is that a high power proton accelerator supplies proton beam to many users simultaneously. This concept can be compared with a facility with many low power proton accelerators for many users. Based on the user demand survey for proton beam applications, we had chosen a facility with a high power accelerator. There are many types of proton accelerator for proton beam applications, such as cyclotron, synchrotron, and linear accelerator. Because the capability of high beam power is the most important feature, we had decided to choose a linear accelerator for the main accelerator of the facility. Figure 1 shows the schematic diagram of the PEFP user beam line.




Figure 1: Schematic diagram.

Proton beams of 100MeV and 20MeV will be extracted and distributed to maximum five users simultaneously by AC magnets with a programmable current power supply. We will control the beam energy stepwise with RF ON/OFF of each DTL tank. To control the beam energy continuously, we will put energy degraders and energy filters in the beam lines for special applications.

2. Beam Line Requirements

The surveys for proton beam demand from many application fields, such as nano-technology (NT), bio-technology (BT), space technology (ST), and radio-isotope production, had been done through the homepage (<http://www.komac.re.kr>) and the user program from 2003 to 2006. From these activities, we had selected the common requirements for many applications and have summarized the beam line requirements for 10 beam lines of 100MeV and 20MeV, which are shown in Table 1 and 2. In the selection process, we had put more weighting to high beam power applications, which will be main applications in this facility.

Table 1: 100MeV beam line requirements

Beam Line No.	Energy	Avg. Current	Irradiation Condition	Max. Target Size
BL100	100MeV	~1.8mA	Horizontal Vacuum	Beam Dump
BL101	33,45,57, 69,80,92, 103MeV	30~ 300μA	Horizontal Vacuum	100mm
BL102	20~ 103MeV	~10μA (10nA)	Vertical External	300mm
BL103	20~ 103MeV	30~ 300μA	Horizontal External	300mm
BL104	20~ 103MeV	10nA ~10μA	Horizontal External	300mm
BL105	103MeV	30~ 300μA	Horizontal Vacuum	100mm

Table 2: 20MeV Beam Line Requirements.

Beam Line No.	Energy	Avg. Current	Irradiation Condition	Max. Target Size
BL20	20MeV	~4.8mA	Horizontal Vacuum	-
BL21	20MeV	120μA ~1.2mA	Horizontal Vacuum	100mm
BL22	3~20MeV	10nA ~60μA	Vertical External	300mm
BL23	3~20MeV	60μA ~1.2mA	Horizontal External	300mm
BL24	20MeV	120μA ~1.2mA	Horizontal Vacuum	100mm
BL25	20MeV	120μA ~1.2mA	Horizontal Vacuum	300mm

3. Beam Line Design

Table 3 shows the beam parameters from the proton linear accelerator, which consists of a 50 keV proton injector, a 3 MeV RFQ, and a 20 MeV DTL [2], and a 100MeV DTL as shown in Figure 1.

Table 3: Beam Parameters.

Energy (MeV)	20	100
Energy spread (%)	< 1%	< 1%
Peak current (mA)	1~20	1~20
Max. beam duty (%)	24	8
Average beam current (mA)	0.1~4.8	0.1~1.6
Pulse width (ms)	0.1~2	0.1~1.33

Max. repetition rate (Hz)	120	60
Max. beam power (kW)	96	160

With the beam line requirements, we had arranged target rooms for beam applications on the experimental hall, which will be 50m wide and 150m long. Figure 2 shows the layout of 20MeV beam lines.




Figure 2: Layout of 20MeV Beam Lines.

A 20MeV proton beam from the Drift Tube Linac (DTL) is transported with bending magnets and quadrupole magnets from linear accelerator tunnel to experimental hall. The first bending magnet for the user beam line is located between two buncher cavities of medium energy beam transport (MEBT) [3] at the end of the 20MeV linear accelerator. Figure 3 is an example of the beam optics calculation from the 20MeV linear accelerator to target room #25 with TRACE-3D [4].




Figure 3: Beam Optics of BL25.

For 100MeV beam lines, the schematic layout is almost same with the 20MeV beam lines. A 100MeV beam is transported through long transport line with doublet lattice from the 100MeV DTL. Figure 4 shows

the beam optics from the linear accelerator to the target room #102.




Figure 4: Beam Optics of BL102.

3. Conclusion

From the results of user demand survey, beam line requirements for 20MeV and 100MeV proton beams from a 100MeV proton linear accelerator to users for beam applications had been prepared. Figure 5 shows the layout of the experimental hall, which is developed with the requirements. The construction will start in 2007, and the operation will start in 2011




Figure 5: PEFP Experimental Hall.

Acknowledgment

This work is supported by the 21st Century Frontier R&D Program of the Ministry of Science and Technology, Republic of Korea

REFERENCES

- [1] Yong-Sub Cho, *et al.*, "100 MeV High-Duty-Factor Proton Linac Development at KAERI," LINAC'06, Knoxville, to be published.
- [2] Hyeok-Jung Kwon, *et al.*, "Test results of the PEFP 20 MeV Proton Accelerator," LINAC'06, Knoxville, to be published.
- [3] Ji-Ho Jang, *et al.*, "Design of the PEFP MEBT," PAC'04, Knoxville, Tennessee, USA 2004.
- [4] K.R. Crandall and D.P. Rusthoi, "TRACE 3-D Documentation," LA-UR-97-886.