

Decommissioning of Activated Reactor Components in Germany and Lessons Learned

Dr. L. Schlömer, B. Könning, T. Eichhorn, P. Sommerer, Dr. Josef Kim Korean Nuclear Society Spring Meeting Jeju, Korea, May 22-23, 2025



Agenda



- Company Presentation
- Decommissioning in Germany

D&D

- Reactor pressure vessel internals
- Reactor pressure vessel
- Activated concrete structures
- Know-How Transfer
- Key Takeaways



About us ...

Academy

- ICOND
- Seminars on nuclear technology, transportation, interim and final storage and the release of radioactive waste
- Cask training NEW in cooperation with GNS!

R&D

- Development of innovative radiation measurement technology and associated software
- Non-destructive material characterization
- Consortium leader in research projects as a central innovation hub
- Research network with universities
- Use of AI in the nuclear environment
- Conducting experiments in our own control area (technical center)

Consulting and Services

- Supporting products from research projects to market readiness
- Qualification of radiation measurement technology for the measurement purpose
- Performing measurements
- Calculations for Radiation protection







Contact

- Technical topics:
 - Dr. Dominik Winter
 - E-mail: <u>winter@nuclear-training.de</u>
 - Phone: +49 (0) 2402 102-1502
- Academy:
 - Helena Schunk
 - E-mail: <u>schunk@nuclear-training.de</u>
 - Phone: +49 (0) 2402 102-1503

Where to find us ...





Where to find us ...





- Peenemünde: Eisenwerke Bassum GmbH
- Sulingen: Eisenwerke Bassum GmbH
- Bassum: Eisenwerke Bassum GmbH
- Essen: GNS Gesellschaft f
 ür Nuklear-Service mbH
- Gladbeck: GNS Power Alloys GmbH
- Mühlheim an der Ruhr: GNS Gesellschaft für Nuklear-Service mbH
- Jülich: WTI Wissenschaftliche-Technische Ingenieurberatung GmbH
- Jülich: GNS Gesellschaft für Nuklear-Service mbH
- Stolberg: Aachen Institute for Nuclear Training (AiNT) GmbH
- Mainhausen: Höfer & Bechtel GmbH
- Alzenau: GNS Gesellschaft f
 ür Nuklear-Service mbH



Korean Nuclear Society Spring Meeting | Jeju, Korea | May 22-23, 2025

Copyright © AiNT GmbH 2025. All righ

Nuclear Power Plants in Germany 2025





0 reactors in operation


- ♦ 21 under decommissioning
- 2 completely dismantled (but storage facility remaining)

Situation: After shut-down all German nuclear power plants have to be decommissioned.

commercial reactors

name	type	operator	start of operation	end of operation
Würgassen	BWR (AEG)	PreussenElektra	11.11.1975	26.08.1994
Unterweser	PWR (KWU, Gen.2)	PreussenElektra	06.09.1979	06.08.2011
Stade	PWR (Siemens-KWU Gen.1)	PreussenElektra	19.05.1972	14.11.2003
Philippsburg 2	PWR (KWU Vor-Konvoi)	EnBW	18.04.1985	31.12.2019
Philippsburg 1	BWR (KWU-Baulinie 69)	EnBW	26.03.1980	06.08.2011
Obrigheim	PWR (Siemens Gen.1)	EnBW	01.04.1969	11.05.2005
Neckarwestheim 2	PWR (KWU Konvoi)	EnBW	15.04.1989	15.04.2023
Neckarwestheim 1	PWR (KWU Gen.2)	EnBW	01.12.1976	06.08.2011
Mülheim-Kärlich	PWR (Babcock-BBC)	RWE	01.10.1987	09.09.1988
Lingen	BWR	RWE	01.10.1986	05.01.1979
Krümmel	BWR (KWU-Baulinie 69)	Vattenfall	28.03.1984	06.08.2011
Isar/Ohu 2	PWR (KWU Konvoi)	PreussenElektra	09.04.1988	15.04.2023
lsar/Ohu 1	BWR (KWU-Baulinie 69)	PreussenElektra	21.03.1979	06.08.2011
Gundremmingen C	BWR (KWU-Baulinie 72)	RWE	18.01.1985	31.12.2021
Gundremmingen B	BWR (KWU-Baulinie 72)	RWE	19.07.1984	31.12.2017
Gundremmingen A	BWR	RWE	12.04.1967	13.01.1977
Grohnde	PWR (KWU Vor-Konvoi)	PreussenElektra	01.02.1985	31.12.2021
Grafenrheinfeld	PWR (KWU Vor-Konvoi)	PreussenElektra	17.06.1982	27.06.2015
Emsland	PWR (KWU Konvoi)	RWE	20.06.1988	15.04.2023
Brunsbüttel	BWR (KWU-Baulinie 69)	Vattenfall	09.02.1977	06.08.2011
Brokdorf	PWR (KWU Vor-Konvoi)	PreussenElektra	22.12.1986	31.12.2021
Biblis B	PWR (KWU Gen.2)	RWE	31.01.1977	06.08.2011
Biblis A	PWR (KWU Gen.2)	RWE	26.02.1975	06.08.2011


Copyright © AiNT GmbH 2025



Classical Project Process



- Most of GNS projects are contracts for a "fleet" of reactors, i. e. reactors of similar type
 → Synergies and learning effects ~ Decommissioning costs ↓
- Typical Split of the projects in "work phases"
 - Work phase 1 Preparation phase
 - Concept development
 - Compilation of the radiological characterization \rightarrow Activation calculations and analyses
 - Preparation of a packaging plan
 - Preparation of a radiation protection concept
 - Obtaining approvals, production & acceptance of the equipment
 - Work phase 2 Execution phase
 - Assembly and installation of equipment,
 - Implementation
 - Cutting/segmentation,
 - packaging,
 - conditioning,
 - Removal of equipment and cleaning,
 - Documentation,
 - Grouting (if necessary)



Projekt "Internals" - Basics



Consortium:

- GNS (leader)
- Westinghouse Germany
- Westinghouse Sweden

Scope of services

Dismantling and packaging of RPV internals (RPV-I) and of core components (operational waste, e.g. control rods) as well as documentation considering final disposal.



pool-protection and cutting table



upper core grid



cutting of upper core grid









core shroud








cutting of lower core grid






Korean Nuclear Society Spring Meeting | Jeju, Korea | May 22-23, 2025

RPV Internals: Equipment Mechanical cutting under water






10

Operational fields for GNS casks in Europe

- Segmented parts must be packed \rightarrow GNS casks
- GNS casks/containers are triple purpose casks transport, storage disposal
- Typical GNS container portfolio used across Europe:
 - MOSAIK[®] and GNS Yellow Box[®] product lines made out of ductile cast iron.
 - Focus: Higher end of the activity levels.
- Steel-sheet containers from Eisenwerk Bassum (GNS-group)
 - Mainly dedicated for the German repository "Konrad"
 → Radioactive inventory restricted by national regulations.
 - Called Konrad Container (KC), since occasionally used outside Germany.
 - Focus: Medium and low activity levels.







Licensing in dealing with local regulators.

- Development of a packaging plan for Taiwanese reactors.
 - Lower container numbers for D&D compared to a D&D plan following the German restrictions (20 Mg).



- Example: New container portfolio for Taiwan ("T-Boxes")
- Development of 5 container types including one type B package covering medium and low activity levels up to the higher end.
- Manufacturing and design according to NQA-1.








Operational fields for GNS casks




Typical fields of application regarding D&D (without decay storage)



Korean Nuclear Society Spring Meeting | Jeju, Korea | May 22-23, 2025

Handling of Parts from Segmentation for Container Loadings

- Lifting tools and baskets for cuboidal or cylindrical containers
- Shielded bell






GNS-Gruppe

GmbH

Copyright © AiNT

Handling of Baskets







Handling of MOSAIK[®] casks for Higher Activated Components











GmbH

Copyright © AiN1

Projekt "ReaDi" - Basics



Contractor:

- GNS group
- Höfer & Bechtel
- GNS


Scope of services

Dismantling and packaging of RPV and insulation as well as documentation considering final disposal





Technical Concept Example: PWR



- Cutting of the primary loop tubes using a wire saw
- Lifting of the RPV into emptied SFP
- Cutting of the RPV using a large bandsaw system and packaging of the parts into steel sheet containers with shielding
- Cutting of the RPV calotte using also the large bandsaw system
- Option: Cutting of the RPV lid advance, in parallel or subsequently using a wire saw



Lifting the RPV






Segmentation of the BWR RPV



- In-situ cutting into rings
- Cutting of the rings on a support frame
- New crane for cut pieces in order to keep the reactor building crane available for other tasks





Packaging



- Loading next to cutting area
- Loading aids to keep cut pieces in place and facilitate later lashing
- Shielded workplace (scaffolding with lead blankets) for lidding of containers outside pool
- Documentation after discharge from the reactor building




D&D of activated concrete structures



- New technical concept based on the use of milling technology.
- This technique is combined with direct suction and filling of the resulting waste product into containers
- Resulting waste product:
 - Concrete debris with defined bulk density
 - Reinforcing bars (iron) is removed by magnets and stored separately or recycled










GmbH 2025.

D&D of activated concrete structures



- Economic advantages compared to conventional technologies:
 - Reduction of execution time → Minimizing transport and logistics operations.
 - Reduction of total dose rate during execution through (semi-)automation of processes
 - Reduction of the required final disposal containers (steel containers) by utilizing the voids during filling.
 - Remaining volumes of already loaded steel containers can be filled with concrete debris.
 - The removal of the concrete surface can be carried out with centimeter precision
 - Significant reduction in the volume of concrete waste to be disposed.
 - The amount of concrete for free release is significantly increased.
- The concept was commissioned by a German customer.
- The implementation phase will begin this year.





Maintaining Expertise and Knowledge Transfer - Core Expertise @ AiNT -



- Lessons Learned Workshops:
 - After each project, a workshop is conducted with the customer to compile insights from the project.
- Developing Solutions:
 - Solutions are developed to make future projects more time and cost-efficient.
- Bundling of know-how in seminar modules that can be offered to external customers
- Seminars modules "Key Facts":
 - Competence building and maintenance through our modular seminar program
 - Expert instructors with practical experience
 - Customer-specific in-house trainings on demand
 - Networking among participants
 - Hybrid solutions
 - Flexible in terms of location
 - Available in English upon request



5 Key Takeaways Based on Ongoing and Completed Projects

- (1) Document Boundary Conditions
 - Clearly document all boundary conditions in advance, including radiological characterization (activation and contamination) and local conditions (ideally via a 3-D laser scan).
- (2) Parallel Preparations
 - Preparations can often be parallelized to save time.
- (3) Fleet Approaches
 - Utilize fleet approaches to transfer proven technologies to nuclear power plants of the same or similar type.
- (4) Logistical Planning
 - Plan loading and dismantling logistically to occur in parallel.
 - Coordinate handling (GNS task) and container removal (customer task).
- (5) Composite Supplier Role
 - The dismantler should ideally also be a composite supplier, designing and manufacturing containers and casks for transport, interim, and final storage of radioactive waste.

If you need support and experience from lessons learned for your D&D projects feel free to ask the GNS group – the market leader in Germany for D&D!









Contact

Dr. Luc Schlömer

schloemer@nuclear-training.de

AACHEN INSTITUTE FOR NUCLEAR TRAINING GMBH (AINT)

Cockerillstraße 100

D-52222 Stolberg (Rheinland)

\$\lambda +49 (0)240210215-00

🖂 info@nuclear-training.de

This document shall not be cited, reproduced in whole or in part, or made available to third parties without the prior written consent of Aachen Institute for Nuclear Training GmbH (AiNT), Stolberg. All rights reserved by AiNT. This document contains trade and/or business secrets of AiNT.



Excellence for **Nuclear**.





Decommissioning of Activated Reactor Components in Germany and Lessons Learned

Dr. L. Schlömer, B. Könning, T. Eichhorn, P. Sommerer, Dr. Josef Kim Korean Nuclear Society Spring Meeting Jeju, Korea, May 22-23, 2025

